

DUPLICATE  
MARKS CLERK  
Intellectual Property

10/532647

European Patent Office  
4220 Washington  
European Trade Mark Attorneys  
Registered Trade Mark Attorneys

Oxford Office  
4220 Washington  
Oxford Business Park South  
Oxford OX4 2RU

Established 1887

Tel: +44 (0)1865 397900  
Fax: +44 (0)1865 397919  
E-mail: oxford@marks-clerk.com  
http://www.marks-clerk.com

Rebecca Tanis  
WesternGeco Intellectual Property Dept  
PO Box 2469  
Houston  
TX 77252-2469  
USA

your ref 14.0209-PCT  
our ref AMS.P52427WO  
date 9 February 2004

RECEIVED

FEB 16 2004

ma/oa/16/04

IPW  
CPA

Dear Rebecca

New PCT Application based on UK patent application No. 0227292.0  
WesternGeco Seismic Holdings Limited et al  
"Implementing a Network Infrastructure in a Seismic Acquisition System"

I am pleased to report that the above PCT application was duly filed at the European Patent Office, in its capacity as a receiving office under the Patent Cooperation Treaty, claiming priority from the basic UK application. I enclose the official filing receipt, the official notification of the international application number and filing date, and a copy of the application as filed.

The filing details of the application are as follows:

Applicant	:	WesternGeco Seismic Holdings Limited et al.
Application No.	:	PCT/EP 03/50871
Filing Date	:	21 November 2003
Priority claimed	:	UK Application No. 0227292.0 of 22 November 2002
States designated	:	All States

Copies of the application are being sent by the Receiving Office to the International Bureau

<b>Partners</b> E W B Lyndon-Stanford MA CPA EPA C J R Gibson CPA EPA D Carpenter LLB CPA EPA K Whalley BSc MITMA CPA EPA P J Alliman BSc MITMA CPA EPA B Spoor BSc CPA EPA M R Higgins BSc MSc CEng MEE MSAE MMEIE CPA EPA D G Tubby BSc CPA EPA E J Godwin MA CPA EPA A J Ablewhite BSc(Cem) ARCS CPA EPA G K Ruffles BA BSc MSc EuChem FRSC CChem CPA EPA J S Robinson MA CPA EPA J A Slater FITMA CPA EPA	A H W Luckhurst MSc MITMA CPA EPA A V Hallam BEng CEng MEE CPA RTMA EPA S P Hosford FITMA R P Harding MA CPA EPA S J Hackett BSc(Phys) ARCS CPA EPA C T Graham LLB MITMA P B Atkinson BSc CChem MRSC CPA EPA H D Lord MA CPA EPA R P Maury MA CPMS MInstP MITMA CPA EPA B J Morgan MITMA K L Hodgkinson MSc(Env) BA(SG) MITMA CPA EPA E D M Rowley FITMA S G Mossey BSc CPA EPA S J Mounteney BSc CPMS MInstP CPA EPA T S Andrews MA PhD CPA EPA	J F Asquith MA FIPA NZPA CPA EPA H C Fisher MITMA D A Every BEng MITMA CPA EPA M P Holmes BSc CPA EPA A V Clarke MA MITMA J Kay LLB MITMA M J Lamb MA FITMA CPA EPA R L Tew BSc MSc MITMA P J Withers BA MITMA I H Coates BSc(Cem) ARCS PhD DIC MITMA CPA EPA A M Suckling MA CPMS RTMA RPA EPA R A Bailey BSc CPA EPA D C Stagg BSc MPhil DIC CPA RTMA EPA J D Collins BSc PhD CPMS MInstP MITMA CPA EPA	S Loeffler BSc(Env) DipEnv MITMA P A Melling BA MITMA R Lind BEng PhD CPA EPA J L Midgley MA MEE CPA EPA R J Granleese MA PhD CPA EPA P C Banford BSc PhD CPA EPA M P Shaw LLB MITMA D I Ward BSc MSc PhD CPA EPA P J Martin BA PhD CPMS CPA EPA J A Moffat BSc CPA EPA MITMA S J Church BEng CPA EPA J Barrett-Major BSc CPA EPA	<b>Associates</b> A C Fairbairn MA CPA EPA K P Halligan MITMA V I Caddy MA MITMA C L Mounteney BA MITMA D Tebbot-Ponsonby MA CPMS CPA EPA G D Smyth MA CPMS MSc CChem CPA EPA P Moran BEng MSc RPA K A Oliver LLB MITMA G D Chisholm BEng(Env) BA(PhD) CPA EPA NZPA S A Duncanson MChem MRSC EPA R J G Oakley MA MSc CPA EPA M P Hagmann-Smith DipEng DipPhys EPA	<b>Consultant</b> M H Blair LLB M J Alge BPhac FSAIBT P Nelson MA Solicitor S M McCausland BEng(Elec XMen) FIPTA NZPA R Ballester Abogado
--	--	--	--	---	--


and to the appropriate International Searching Authority (the European Patent Office), and we shall write to you further when we receive the International Search Report.

The European Patent Office has not asked for replacement drawings to be filed, and the UK Patent Office has accepted the original drawings on the corresponding UK application. I am not, therefore, preparing replacement drawings on this case.

Thank you for returning the four authorisations so far for this application. I look forward to receiving the remaining authorisation – from Ove Brynestad – in due course. The deadline for filing this authorisation at the EPO is 21 March 2004.

Please let me know if you have any questions concerning this application. A note of our charges is being sent to WesternGeco AS.

Yours sincerely



**Dr Andrew Suckling**  
for Marks & Clerk



Europäisches  
Patentamt

European  
Patent Office

Office européen  
des brevets

### Acknowledgement of receipt

We hereby acknowledge receipt of your request for the processing of an international application according to the Patent Cooperation Treaty as follows:

Submission number	9706	
PCT application number	PCT/EP03/50871	
Date of receipt	21 November 2003	
Receiving Office	European Patent Office, The Hague	
Your reference	AMS.P52427WO	
Applicant	WESTERNGECO SEISMIC HOLDINGS LIMITED	
Number of applicants	5	
Country		
Title	IMPLEMENTING A NETWORK INFRASTRUCTURE IN A SEISMIC ACQUISITION SYSTEM	
Documents submitted	Fees:PDF application-body.xml di450_0311211630.pdf p52427wo.zip pct101.GML request.xml	Pct101.PDF di450_0311211624.pdf fee-sheet.xml package-data.xml pct101u.GML
Submitted by	CN=A. Suckling,O=Marks & Clerk,C=GB	
Method of submission	Online	
Date and time receipt generated	21 November 2003, 18:07:58	
Digest	8F:2F:F2:D4:3A:4A:FA:44:50:26:E4:33:BE:CA:C5:4B:3B:0A:68:1F	

/European Patent Office/

# PATENT COOPERATION TREATY

From the RECEIVING OFFICE

# PCT

To:

Suckling, Andrew  
MARKS & CLERK  
4220 Nash Court  
Oxford Business Park South  
Oxford OX4 2RU  
GRANDE BRETAGNE

NOTIFICATION OF THE INTERNATIONAL  
APPLICATION NUMBER AND OF THE  
INTERNATIONAL FILING DATE

(PCT Rule 20.5(c))

Date of mailing  
(day/month/year)

21 JAN 2004

Applicant's or agent's file reference  
AMS.P52427W0

IMPORTANT NOTIFICATION

International application No.  
PCT/EP03/50871

International filing date (day/month/year)  
21/11/2003

Priority date (day/month/year)  
22/11/2002


Applicant  
WESTERNGECO SEISMIC HOLDINGS LIMITED

Title of the invention

1. The applicant is hereby notified that the international application has been accorded the international application number and the international filing date indicated above.
2. The applicant is further notified that the record copy of the international application was transmitted to the International Bureau on the above date of mailing.

3. ☐ Other: \_\_\_\_\_

\* The International Bureau monitors the transmittal of the record copy by the receiving Office and will notify the applicant (with Form PCT/IB/301) of its receipt. Should the record copy not have been received by the expiration of 14 months from the priority date, the International Bureau will notify the applicant (Rule 22.1(c)).

Name and mailing address of the Receiving Office  
 European Patent Office, P.B. 5818 Patentlaan 2  
NL-2280 HV Rijswijk  
Tel. (+31-70) 340-2040  
Fax: (+31-70) 340-3016

Authorized officer

O. Gorge

## PCT REQUEST

Duplicate of original printed on Friday, 21 November, 2003 03:39:41 PM

0	For receiving Office use only	
0-1	International Application No.	PCT/EP03 / 50871
0-2	International Filing Date	(21.11.2003) 21 NOV 2003
0-3	Name of receiving Office and "PCT International Application"	OFFICE EUROPEEN DES BREVETS DEMANDE INTERNATIONALE PCT
0-4	Form - PCT/RO/101 PCT Request	
0-4-1	Prepared using	epoline® online filing PCT plug-in (updated 07.10.2003)
0-5	Petition The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty	
0-6	Receiving Office (specified by the applicant)	European Patent Office (EPO) (RO/EP)
0-7	Applicant's or agent's file reference	AMS.P52427WO
I	Title of invention	IMPLEMENTING A NETWORK INFRASTRUCTURE IN A SEISMIC ACQUISITION SYSTEM
II	Applicant	
II-1	This person is:	applicant only
II-2	Applicant for	AP: (GH GM KE LS MW MZ SD SL SZ TZ UG ZM ZW); EA: (AM AZ BY KG KZ MD RU TJ TM); EP: (AT BE BG CH&LI CY CZ DE DK EE ES FI GB GR HU IE IT LU MC NL PT RO SE SI SK TR); OA: (BF BJ CF CG CI CM GA GN GQ GW ML MR NE SN TD TG); AE AG AL AM AT AU AZ BA BB BG BR BY BZ CA CH&LI CN CO CR CU CZ DE DK DM DZ EC EE EG ES FI GB GD GE GH GM HR HU ID IL IN IS JP KE KG KP KR KZ LC LK LR LS LT LU LV MA MD MG MK MN MW MX MZ NI NO NZ OM PG PH PL PT RO RU SC SD SE SG SK SL SY TJ TM TN TR TT TZ UA UG UZ VC VN YU ZA ZM ZW + BW <sup>4</sup>
II-4	Name	WESTERNGECO SEISMIC HOLDINGS LIMITED
II-5	Address:	PO Box 71 Craigmuir Chambers Road Town Tortola Virgin Islands, British
II-6	State of nationality	[GB] <sup>4</sup> VG <sup>44</sup>
II-7	State of residence	[GB] <sup>4</sup> VG <sup>44</sup>

RO/EP

RO/EP  
RO/EP

## PCT REQUEST

AMS.P52427WO

Duplicate of original printed on Friday, 21 November, 2003 03:39:41 PM

<b>III-1</b>	<b>Applicant and/or inventor</b>	
III-1-1	This person is:	applicant only
III-1-2	Applicant for	EP: (FR)
III-1-4	Name	SERVICES PETROLIERS SCHLUMBERGER
III-1-5	Address:	42, rue de Saint Dominique F-75007 Paris France
III-1-6	State of nationality	FR
III-1-7	State of residence	FR
<b>III-2</b>	<b>Applicant and/or inventor</b>	
III-2-1	This person is:	applicant and inventor
III-2-2	Applicant for	US only
III-2-4	Name (LAST, First)	ARNEGAARD, Truls
III-2-5	Address:	Markveien 1 N-0554 Oslo Norway
III-2-6	State of nationality	NO
III-2-7	State of residence	NO
<b>III-3</b>	<b>Applicant and/or inventor</b>	
III-3-1	This person is:	applicant and inventor
III-3-2	Applicant for	US only
III-3-4	Name (LAST, First)	BRYNESTAD, Ove
III-3-5	Address:	Aannerudskogen 125 N-1383 Asker Norway
III-3-6	State of nationality	NO
III-3-7	State of residence	NO
<b>III-4</b>	<b>Applicant and/or inventor</b>	
III-4-1	This person is:	applicant and inventor
III-4-2	Applicant for	US only
III-4-4	Name (LAST, First)	VIRGIN, Brian, Lee
III-4-5	Address:	Kirkeveien 220B N-1383 Asker Norway
III-4-6	State of nationality	US
III-4-7	State of residence	NO

## PCT REQUEST

AMS.P52427WO

Duplicate of original printed on Friday, 21 November, 2003 03:39:41 PM

IV-1	Agent or common representative; or address for correspondence The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:	agent
IV-1-1	Name (LAST, First)	SUCKLING, Andrew
IV-1-2	Address:	Marks & Clerk 4220 Nash Court Oxford Business Park South Oxford, Oxfordshire OX4 2RU United Kingdom
IV-1-3	Telephone No.	+44(0)1865 397900
IV-1-4	Facsimile No.	+44(0)1865 397919
IV-1-5	e-mail	asuckling@marks-clerk.com
V	Designation of States	
V-1	Regional Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AP: GH GM KE LS MW MZ SD SL SZ TZ UG ZM ZW and any other State which is a Contracting State of the Harare Protocol and of the PCT + BW <sup>A</sup> EA: AM AZ BY KG KZ MD RU TJ TM and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT EP: AT BE BG CH&LI CY CZ DE DK EE ES FI FR GB GR HU IE IT LU MC NL PT RO SE SI SK TR and any other State which is a Contracting State of the European Patent Convention and of the PCT OA: BF BJ CF CG CI CM GA GN GQ GW ML MR NE SN TD TG and any other State which is a member State of OAPI and a Contracting State of the PCT
V-2	National Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AE AG AL AM AT AU AZ BA BB BG BR BY BZ CA CH&LI CN CO CR CU CZ DE DK DM DZ EC EE EG ES FI GB GD GE GH GM HR HU ID IL IN IS JP KE KG KP KR KZ LC LK LR LS LT LU LV MA MD MG MK MN MW MX MZ NI NO NZ OM PG PH PL PT RO RU SC SD SE SG SK SL SY TJ TM TN TR TT TZ UA UG US UZ VC VN YU ZA ZM ZW + BW <sup>A</sup>

A  
PO/EPA  
PO/EP

## PCT REQUEST

AMS.P52427WO

Duplicate of original printed on Friday, 21 November, 2003 03:39:41 PM

V-5	<b>Precautionary Designation Statement</b> In addition to the designations made under items V-1, V-2 and V-3, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except any designation(s) of the State(s) indicated under item V-6 below. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit.		
V-6	<b>Exclusion(s) from precautionary designations</b>	NONE	
VI-1	<b>Priority claim of earlier national application</b>		
VI-1-1	Filing date	22 November 2002 (22.11.2002)	
VI-1-2	Number	0227292.0	
VI-1-3	Country	GB	
VII-1	<b>International Searching Authority Chosen</b>	European Patent Office (EPO) (ISA/EP)	
VIII	<b>Declarations</b>	Number of declarations	
VIII-1	Declaration as to the identity of the inventor	-	
VIII-2	Declaration as to the applicant's entitlement, as at the international filing date, to apply for and be granted a patent	-	
VIII-3	Declaration as to the applicant's entitlement, as at the international filing date, to claim the priority of the earlier application	-	
VIII-4	Declaration of inventorship (only for the purposes of the designation of the United States of America)	-	
VIII-5	Declaration as to non-prejudicial disclosures or exceptions to lack of novelty	-	
IX	<b>Check list</b>	number of sheets	electronic file(s) attached
IX-1	Request (including declaration sheets)	5	-
IX-2	Description	20	di450_0311211630.pdf
IX-3	Claims	4	di450_0311211630.pdf
IX-4	Abstract	1	di450_0311211630.pdf
IX-2b	Pre-conversion archive	-	p52427wo.zip
IX-5	Drawings	8	di450_0311211624.pdf
IX-7	TOTAL	38	



## PCT REQUEST

AMS.P52427WO

Duplicate of original printed on Friday, 21 November, 2003 03:39:41 PM

	Accompanying Items	paper document(s) attached	electronic file(s) attached
IX-8	Fee calculation sheet	-	Fees . PDF
IX-19	Figure of the drawings which should accompany the abstract	3	
IX-20	Language of filing of the international application	English	
X-1	Signature of applicant, agent or common representative	Subject: GB, Marks & Clerk, A. Suckling Issuer: DE, D-Trust GmbH, D-Trust for EPO 2.0 Authorised Representative (Agent 1)	
X-1-1	Signed by		
X-1-2	Capacity		

## FOR RECEIVING OFFICE USE ONLY

10-1	Date of actual receipt of the purported international application	(21.11.2003)	21 NOV 2003
10-2	Drawings:	✓	
10-2-1	Received		
10-2-2	Not received		
10-3	Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application		
10-4	Date of timely receipt of the required corrections under PCT Article 11(2)		
10-5	International Searching Authority	ISA/EP	
10-6	Transmittal of search copy delayed until search fee is paid		

## FOR INTERNATIONAL BUREAU USE ONLY

11-1	Date of receipt of the record copy by the International Bureau	
------	--	--

## IMPLEMENTING A NETWORK INFRASTRUCTURE IN A SEISMIC ACQUISITION SYSTEM

### BACKGROUND OF THE INVENTION

#### 1. FIELD OF THE INVENTION

The present invention pertains to seismic surveys, and, more particularly, implementing a network infrastructure in a seismic acquisition system.

#### 2. DESCRIPTION OF THE RELATED ART

Seismic acquisition systems typically are used in seismic surveys. In a seismic survey, an array of seismic receivers is deployed in a selected area. One, and usually more, seismic sources are also deployed. The sources impart acoustic signals into the ground that are reflected and refracted by subterranean formations back to the receivers. The receivers then transmit data indicative of selected characteristics of the reflections to a data collection system. The data collection system then collects the data, processes and/or pre-processes it, and, typically, transmits to another location for further processing.

Seismic surveys can be generally categorized as land-based and water-based (or, "marine"), *i.e.*, by whether they are conducted on land or in the water. Each implicates challenges unique from the other. For instance, in a marine survey, the seismic sources are usually towed at or near the surface of the water. The acoustic signals must therefore propagate through the water before they are imparted into the ground, or sea floor. In contrast, sources in a land-based survey can impart the acoustic signals directly into the ground.

However, there are also numerous challenges arising from both these kinds of surveys. One challenge is to accurately know the physical position of the sources when they impart the acoustic signals and of the receivers when they receive the reflections. Also, a modern seismic acquisition operation requires data to be collected from a large number of individual units; sources, position sensors, seismic sensors, *etc.* These units act as data sources in the operation. Usually a number of separate data collecting systems are involved in the operation, each employing their own infrastructure and method for connecting the data

sources to the data collecting systems. These connectivity infrastructures are optimised to be fit for their particular purpose, and have therefore often wildly differing characteristics and means of operation. Introducing a new data source, and/or a new data collecting system into the operation requires the introduction of a new connectivity infrastructure, adding complexity to the total system. Alternatively, an existing infrastructure may be adapted to carry the new information. However, this will often be a complex task in itself.

The present invention is directed to resolving, or at least reducing, one or all of the problems mentioned above.

### **SUMMARY OF THE INVENTION**

The invention, in its various aspects and embodiments, comprises a method and apparatus implementing a network infrastructure in a seismic acquisition system. The apparatus is a seismic acquisition system, comprising a plurality of seismic data sources capable of generating data; at least one data collection system utilizing an open network protocol; and at least one line network connecting the data sources to the data collection system and utilizing an open network protocol. The line network includes a plurality of data source nodes at which a portion of the plurality of seismic data sources are respectively attached to the line network; and a router for routing data generated by the seismic data sources to the data collection system through the data source nodes in accordance with the open network protocol. The method comprises assigning at least two respective network addresses to each one of a plurality of seismic data sources, a plurality of data source nodes, a plurality of routers, and a data collection system; routing data generated by the data sources through the data source nodes and the routers to the data collection system; correlating the network addresses of the seismic data sources to the physical location of the respective seismic data sources; and correlating the physical locations of the respective seismic data sources to the data generated by the respective seismic data sources.

### **BRIEF DESCRIPTION OF THE DRAWINGS**

The invention may be understood by reference to the following description taken in conjunction with the accompanying drawings, in which like reference numerals identify like elements, and in which:

**FIG. 1** depicts the conduct of a seismic survey in accordance with one aspect of the present invention including a recording array connected to a data collection system;

**FIG. 2A** conceptually depicts a computing system such as may be used in implementing certain aspects of the present invention—namely, portions of the data collection system;

**FIG. 2B** is a block diagram of selected components of the hardware and software architectures of the computing system in **FIG. 2A**;

**FIG. 3** illustrates a single line network, the elemental building block of the recording array in **FIG. 1**, connected to the data collection system;

**FIG. 4** illustrates one particular implementation of the recording array in **FIG. 1** in which multiple line networks, such as that illustrated in **FIG. 3**, are employed to facilitate fault tolerance and spread coverage;

**FIG. 5A** illustrates timing domains of a synchronization technique employed in one particular implementation of the recording array in **FIG. 1** in accordance with the Network Time Protocol (“NTP”) of the Internet Protocol (“IP”) suite of protocols;

**FIG. 5B** illustrates a synchronization technique alternative to that in **FIG. 5A**;

**FIG. 6** depicts one embodiment of a method for use in a seismic survey in accordance with the present invention; and

**FIG. 7A** and **FIG. 7B** illustrate the use of the present invention in a land-based seismic survey in one particular embodiment.

While the invention is susceptible to various modifications and alternative forms, the drawings illustrate specific embodiments herein described in detail by way of example. It should be understood, however, that the description herein of specific embodiments is not intended to limit the invention to the particular forms disclosed, but on the contrary, the intention is to cover all modifications, equivalents, and alternatives falling within the spirit and scope of the invention as defined by the appended claims.

### **DETAILED DESCRIPTION OF THE INVENTION**

Illustrative embodiments of the invention are described below. In the interest of clarity, not all features of an actual implementation are described in this specification. It will of course be appreciated that in the development of any such actual embodiment, numerous implementation-specific decisions must be made to achieve the developers' specific goals,

such as compliance with system-related and business-related constraints, which will vary from one implementation to another. Moreover, it will be appreciated that such a development effort, even if complex and time-consuming, would be a routine undertaking for those of ordinary skill in the art having the benefit of this disclosure.

**FIG. 1** depicts the conduct of a seismic survey system 100 in accordance with one aspect of the present invention. The seismic survey system 100 is a land-based survey system. The seismic survey system 100, accordingly, includes a recording truck 105 connected to a seismic array 110, which is a recording array in the illustrated embodiment. The recording array 110 includes a plurality of seismic data sources 120, such as, for example, seismic sources (*e.g.*, vibrators, explosive charges), positioning sensors (Global Positioning System ("GPS") sensors), seismic receivers (geophones), *etc.*, on a plurality of lines 125. More typically, however, seismic sources, *e.g.*, the seismic source 115, are not a part of the recording array 110. The recording array 110 also includes a plurality of nodes 130 and at least one router 135, whose function will be discussed further below.

The seismic survey system 100 includes at least one data collection system 140. Note that some alternative embodiments may employ multiple data collection systems 140. The recording truck 105 is equipped with a rack-mounted computing apparatus 200, illustrated in **FIG. 2A** and **FIG. 2B**, with which at least a portion of data collection system 140 is implemented. The computing apparatus 200 includes a processor 205 communicating with some storage 210 over a bus system 215. The storage 210 may include a hard disk and/or random access memory ("RAM") and/or removable storage such as a floppy magnetic disk 217 and an optical disk 220. The storage 210 is encoded with a data structure 225 storing the data set acquired as discussed above, an operating system 230, user interface software 235, and an application 265. The user interface software 235, in conjunction with a display 240, implements a user interface 245. The user interface 245 may include peripheral I/O devices such as a key pad or keyboard 250, a mouse 255, or a joystick 260. The processor 205 runs under the control of the operating system 230, which may be practically any operating system known to the art.

The application 265 is invoked by the operating system 230 upon power up, reset, or both, depending on the implementation of the operating system 230, to administer an open

network protocol on the recording array 110. The administration of this open network protocol imposes a network infrastructure on the seismic acquisition system 100 with which the seismic survey is being conducted. A network, in a general sense, is a plurality of functionally interconnected computing systems. Note that a computing system may be as simple as a single computing device (e.g., a controller or processor) or as complex as many individual computers. A network protocol (or, more simply, a "protocol") is an agreed upon format for transmitting information between computing devices. A protocol typically specifies transmission characteristics such as error checking, data compression, end of message indicators, and return receipts. Practically any open network protocol may be employed, but one particular implementation employs, e.g., the Internet Protocol ("IP") suite. "Open" standards are simply standards promulgated by industry groups that are available to the public. The IP protocol suite, in particular, specifies a format for "packets," or datagrams, that may be addressed to a recipient and then dropped into the network for delivery.

Thus, in the illustrated embodiment, a single IP-based network (i.e., the recording array 110, data collection system 140) is deployed between the different data sources 120 and data collection system(s) 140, allowing communication between data sources 120 and data collection system(s) 140 over any protocol supported on top of IP, which includes most modern, open protocols. In addition, the node-to-node nature of such a spread network allows communication between the plurality of data sources 120 and, separately, between the plurality of data collection system(s) 140, thereby opening a broad range of possible applications. Several features of the IP protocol suite are particularly useful as applied to the seismic acquisition scenario. The generic and wide-spread nature of IP simplifies adapting new services and applications to the seismic acquisition system. The protocols comprising the IP protocol suite support dynamically update routing information, which is important in supporting fault tolerance and high availability.

FIG. 3 illustrates a single line network 300, the elemental building block of the recording array 110 in FIG. 1, connected to the data collection system 140. The line network 300 comprises a single router 135 connected between the data collection system 140 and a plurality of nodes 130. The nodes 130 are connected to the line 125. Each node 130 is, in turn, connected to a string 305 of data sources 120. The data sources 120 may be any mix and match of the typical types of equipment used in seismic surveys, e.g., sources, position

sensors, seismic sensors, *etc.* Each of the data collection system 140, the router 135, the nodes 130, and the data sources 120 is assigned a unique, network address in accordance with the network protocol administered by the data collection system 140.

The data source nodes 130 themselves are connected by means of a medium-bandwidth, IP-based network. The data source nodes 130 will typically be intelligent units, capable of both initiating and participating in communications sessions with other data source nodes 130 and with the data collection system(s) 140. The data source nodes 130 are connected in-line, each data source node 130 connected to at most two neighbouring data source nodes 130 in the illustrated embodiment. A number of data source nodes 130 will typically be connected together, forming a string of data source nodes 130, as will be discussed further below. Terminating such a string will be a network router 135. The router 135 is a computing device that connects multiple, relatively small networks—such as the line network 300—together. Multiple line networks 300, other routers 135, or data collection systems 140 may be connected to a single router 135.

The seismic data sources 120 package data into packets (not shown), each of which contains not only data, but a variety of other information. Some of this information is in what is known as the “header” of the packet. The header typically contains the network address of the destination for the packet, *e.g.*, the data collection system(s) 140. The router 135 uses this information in the headers of the packets from the seismic data sources 120 and a lookup table (not shown) stored on router 135 to determine the packet’s destination. The router 135 then communicates with other routers 135 to determine the best path to that destination through the larger network as a whole. In the illustrated embodiment, the routers 135 communicate among each other using a second open protocol called Open Shortest Path First (“OSPF”), although alternatives might include Internet Control Message Protocol (“ICMP”), which is a well known extension to the IP protocol suite. Still other open protocols may be used in alternative embodiments. Thus, the router 135 behaves in the illustrated embodiment as a standard IP network router, routing traffic to and from the data source nodes 120 on the line networks 300 connected to the router 135, as well as traffic to and from the other routers 135 connected to it.

The connections among the seismic data sensors 120, seismic source nodes 130, the router 135, and the data collection system 140 are all designed to accommodate the amount of network traffic expected to be travelling thereon. The line 125 implements, in the illustrated embodiment, a medium-bandwidth data path. The connection 310 is a high-bandwidth data path, sometimes referred to in networking parlance as the "backbone." In the illustrated embodiment, the connection 310 and the line 125 are both electrical, and may be implemented using any suitable electrical technology known to the art. For instance, twisted wire pairs and shielded coaxial cables might be employed in various embodiments. However, this is not required for the practice of the invention. The connection 310 and line 125 may alternatively be optical fibres, for instance, or a wireless system.

The precise parameters regarding the bandwidth of the line 125 and connection 310 will be implementation specific, depending on the number of components (*e.g.*, seismic data sources 120, data source nodes 130, routers 135, and data collection systems 140), the particular protocol implemented, and the structure of the recording array 110. However, those in the art having the benefit of this disclosure will be able to readily determine these parameters based on standard networking principles and the specifications of the applicable protocols. Furthermore, whether the line 125 or the connection 310 is "high" bandwidth or "medium" bandwidth is not material to the practice of the invention so long as they have the capacity to handle the traffic thereon for the given implementation.

Although the line network 300 of FIG. 3 can be used in isolation to conduct a survey, a recording array (*e.g.*, the recording array 110 in FIG. 1) will typically comprise several line networks 300. FIG. 4 illustrates one particular implementation 400 of the recording array 110 in FIG. 1 in which multiple line networks, such as the line network 300 in FIG. 3, are employed to facilitate fault tolerance and spread coverage. The degree of fault tolerance and/or spread coverage will be highly implementation specific, depending on the number and arrangement of the line networks 300 therein. Note, however, that various alternative embodiments may employ the invention without necessarily using this "modular" approach.

More particularly, the survey apparatus 400 includes multiple data collection units 140 (*i.e.*, DC<sub>0</sub>-DC<sub>3</sub>), multiple routers 135 (*i.e.*, R<sub>0</sub>-R<sub>11</sub>), multiple data source nodes 130 (*i.e.*, N<sub>0</sub>-N<sub>15</sub>), and multiple seismic data sources 120 (*i.e.*, S<sub>0</sub>-S<sub>31</sub>). Note that the precise numbers



of the different types of components is not material to the practice of the invention, nor are the ratios. For instance, an alternative embodiment might employ only a single data collection unit for the same number of routers, data source nodes, and seismic data sources. The precise numbers of the various pieces of equipment will be implementation specific. Note that, although not necessarily required to practice the invention, each router 135 is connected to a data collection system 140 by a backbone 310.

In the embodiment of **FIG. 4**, a break in more than one line or backbone will be survivable as long as more than one backbone and line are available, and they do not affect the same line; not all backbones are broken at the same link 'latitude'; and not all lines are broken. For instance:

- a break between the router  $R_3$  and the data source node  $N_4$  and a break between the data source node  $N_5$  and the router  $R_4$  (*i.e.*, in the same link "latitude") will drop the data source nodes 130 (*e.g.*,  $N_4$ ,  $N_5$ ) and the associated seismic data sources 120 (*e.g.*,  $S_8$ - $S_{11}$ ) from the survey; and
- a break in the backbone 310 between the routers  $R_3$ ,  $R_6$ , in the backbone 310 between the routers  $R_4$ ,  $R_7$ , and in the backbone between the routers  $R_5$ ,  $R_8$  will drop all components "below" the routers  $R_3$ - $R_5$  from the survey.

In general, however, the survey apparatus 400 exhibits relatively high fault tolerance. Furthermore, combinations of line and backbone network link failures may be survivable depending on the exact locations of the breaks.

Additional data collection systems 140 can be added to the spread network at any router 135. There may be more than one data collection system 140 connected, and the data collection systems 140 (*e.g.*,  $DC_2$ ,  $DC_3$ ) may be connected at separate routers 135. The data collection systems 140 (*e.g.*,  $DC_1$ ,  $DC_2$ ,  $DC_3$ ) serve as local data collection points collecting data off a respective backbone that they then forward to a designated, central collection data system 140 (*e.g.*,  $DC_0$ ). The physical area that may be covered by a spread network (*e.g.*, the spread network 400) will be limited by the distance limitations of the network hardware. In addition, it may be limited by the maximum bandwidth of the line network. The routers 135 may be connected to more than one line network (*e.g.*,  $R_1$ ,  $R_4$ ,  $R_7$ ,  $R_{10}$ ), thus it will be possible to extend the spread network beyond the limitations of one line network by adding multiple line networks in the in-line direction. To utilize such a topology one might either

add multiple high bandwidth network links to one data collection system 140 as in FIG. 1, or add multiple, parallel, data collection systems 140 that collect data from separate parts of the spread network as in FIG. 4.

Another advantage of the spread network of the present invention is that dynamic routing and load balancing techniques can be used to determine which data collection system 140 a given seismic data source 120 should communicate with. Depending on the configuration and topology of the spread network, different channels, routers 135, or data collection systems 140 might receive different levels of traffic. At different times, some routers 135 or data collection systems 140 may be busy while others may be idle. Some might even be borderline overwhelmed by the level of traffic. The traffic load on various components such as routers 135 and data collection systems 140 might also vary over time from very busy to very idle. For instance, traffic levels may change over time as new seismic data sources 120 are added, old ones removed, or network failures impact the performance of the spread network.

Dynamic routing and load balancing techniques have been developed for computing networks to accommodate these types of concerns. These techniques monitor network traffic patterns and adjust network operation to ameliorate the burdens on individual components. These techniques can be applied to the spread network of the present invention to help order traffic therein, adapt to unforeseen exigencies such as equipment failures. Dynamic routing and auto configuration of the network will also facilitate varying the layout and topology of the spread network. This will be particularly useful in "rolling" the spread during seismic operations.

The open standard-based IP network of the illustrated embodiment is extended with three features adapted to the seismic acquisition environment. One is a synchronization service allowing different data source nodes 130 on the spread network (*e.g.*, 100 or 400) to have real-time clocks that are closely synchronized. Seismic surveying, in general, employ tighter synchronization than do the computing networks for which the open-protocols have been developed. Hence, the use of the synchronization service. The second is a location mapping service enabling the spread network to easily convert a network address to a logical location and *vice versa*. Seismic surveying also "peg maps" the logical location of the

seismic data sources 120 to their location in the network. Thirdly, the spread network will support auto-configuration of the network infrastructure itself, *e.g.* not only will it be possible to dynamically add and remove clients (end-points) from the active network, but also routers. This is useful not only when performing maintenance and repair of malfunctioning components, but also when 'rolling' the seismic spread during normal seismic surveying operations.

Turning first to the synchronization service, FIG. 5A illustrates timing domains employed in one particular implementation of the recording array 110 in FIG. 1. This particular embodiment employs the Network Time Protocol ("NTP") of the Internet Protocol ("IP") suite of protocols. NTP assures accurate synchronization to the millisecond of computer clock times in a network of computers. In a standard networking application, NTP synchronizes client workstation clocks to the U.S. Naval Observatory Master Clocks in Washington, D.C. and Colorado Springs, Colorado. Running as a continuous background client program on a computer, NTP sends periodic time requests to servers, obtaining server time stamps and using them to adjust the client's clock. The present invention employs NTP in the same fashion.

The IP protocol NTP is extended with propagation delay measurement to provide sub microsecond accuracy. One data collection system 140 is assigned to be the active synchronization master at any one time. The active synchronization master is referred to as "Stratum 1" in NTP parlance. Synch masters will have access to an external accurate time source (*e.g.*, a Global Positioning System, or "GPS," receiver) referred to as "Stratum 0." Alternate synch masters can be defined, and they can use the mechanism for time distribution described below to verify the integrity of their respective time sources.

More particularly, the underlying network implementation supplies accurate time distribution and clock synchronization features. These primitives are used to recursively distribute the real-time as supplied by an "active synchronization master." First, the primitives transmitted iteratively from the active synchronization master (stratum 1) to the router on the backbone connected to the master. This router will then be a backbone network synch master (stratum 2) and will synchronize all routers on the backbone (stratum 3). Subsequently, each router will synchronize all line nodes connected to it (stratum 3 or 4).

Only the backbone to which the synch master of the moment is connected will be synchronized directly from the active synchronization master. Other backbone networks will have their own network synch masters. These network synch masters will take synch from the line network connecting them to the higher-level stratum. Data collection systems connected to the spread network can be configured to be synchronization clients, *e.g.*, they can be accurately synchronized with the line nodes, and with other data collection systems without having their own time reference systems.

Returning now to FIG. 5A, the spread network 500 comprises multiple data collections systems DC, routers R, data source nodes N, and seismic data sources S as discussed above. The spread network 500 also includes a GPS receiver 502 that provides a clock CLK for the spread network 500. The spread network 500 comprises a plurality of synchronization strata 504 defined as described above in accordance with the NTP IP protocol. The strata 504 are designated STRATUM<sub>0</sub> - STRATUM<sub>5</sub>. The GPS receiver 502 is STRATUM<sub>0</sub>. The data collection system 506, connected to the GPS receiver 502, is the designated synchronization master and constitutes STRATUM<sub>1</sub>. The data collection system 508 and router 510, connected between the data collection system 506 and the rest of the spread network 500, constitutes STRATUM<sub>2</sub>. The line network 512 of the routers 514, 516, 518 are connected between STRATUM<sub>2</sub> and the rest of the spread 500. They consequently constitute STRATUM<sub>3</sub>. Similarly, the line networks 520, 522, 524 of the routers 514, 516, 518, respectively, constitute STRATUM<sub>4</sub>. The routers 526, 528, 530 are also a part of STRATUM<sub>4</sub>. Finally, the line networks 532 and 534 of the routers 528, 530, respectively, and the routers 536, 538 constitute STRATUM<sub>5</sub>.

The synchronization begins as the data collection system 506, acting as the active synchronization master, passing the primitives to STRATUM<sub>2</sub>. The data collection system 508 and router 510 are then synchronized to the clock of the data collection system 506. The router 510 then assumes the role of "backbone network synch master" for the backbone 540 and the routers 516 and 518 on the backbone 540. The router 510 is also the synch master for the router 514 on the line network 512. As mentioned above, each router R synchronizes the lines nodes, including both data source nodes N and routers R, on the lines to which it is connected.

Thus, the router 510 passes the primitives to each of the routers 514, 516, 518 in STRATUM<sub>3</sub>. Each of the routers 514, 516, 518, in turn, then passes the primitives to the line nodes on the lines connected thereto. The router 514 therefore passes the primitives to the nodes N and routers R on the line network 520, the router 516 does the same on the line network 522, and the router 518 for the line network 524. Thus, the routers 526, 528, 530 in STRATUM<sub>4</sub> are synched to the routers 514, 516, 518, respectively, in STRATUM<sub>3</sub>. The routers 528, 530 then pass the primitives to the routers 536, 538, respectively, in STRATUM<sub>5</sub>. If additional line networks and/or routers and/or data collection systems are added, they can be synchronized to the rest of the spread network 500 in the same iterative fashion across additional strata defined in accordance with the NTP protocol.

It can be shown that the synchronization error of this approach is proportional to  $\sqrt{n_{hops}}$  where  $n_{hops}$  is the number of discrete network link hops from stratum 0. As will be appreciated by those skilled in the art having the benefit of this disclosure, a "network link hop" occurs with the regeneration of network time stamps using local real-time clocks. Thus, in the embodiment of FIG. 5A, there is a "network link hop" between each of the strata STRATUM<sub>0</sub> - STRATUM<sub>5</sub>. The hierarchical scheme imposed by the NTP protocol keeps  $n_{hops}$  small relative to the total size of the spread network 500. Note that alternate routing for synchronization is possible using exactly the same fail over and rerouting protocols as for data traffic. That is, in FIG. 5A, a node N (e.g., the node 542) will by default be synchronized by a router R (e.g., the router 514). But, another router R (e.g., the router 510) is also available and able to supply synchronization to the node N, albeit in a higher stratum. The ability to supply synchronization along multiple paths also allows time and synchronization verification in the spread network 500. This may be done, e.g., by comparing multiple synchronization sources against each other.

An alternative synchronization technique is illustrated in FIG. 5B. The underlying principle of this spread synchronization technique is "Local Real Time Clock" ("RTC") adjustment using:

- timestamps, corresponding to uniquely identifiable transmission events, distributed by one or more synchronization masters;
- RTC sampling by synchronization slaves triggered by the corresponding reception events;

- deterministic propagation delay separating transmission and reception events; and
- measurement of this propagation delay.

The local RTC error is assumed to be the difference between the locally measured reception time and (timestamp + propagation delay). The illustrated embodiment assumes that the transmission event used for synchronization is the moment at which the first bit of the frame containing a timestamp is clocked onto the line.

RTC synchronization with (sub) micro second accuracy is desirable for seismic acquisition. This level of accuracy generally cannot be achieved if propagation delays, timestamp generation and RTC sampling are not sufficiently deterministic, as is the case with NTP. Fault tolerance and auto configurability generally cannot be achieved if timestamps are distributed by a single source along fixed routes whose delays are measured during system boot. Similarly, bit synchronous networks, where local transmission clocks are derived from those recovered from incoming signals, couple spread synchronization to the initial spread topology.

The primary techniques for decoupling spread synchronization from global topology in the illustrated embodiment are:

- regenerating timestamps throughout the spread using local RTCs;
- controlling local transmission clock signals locally; and
- measuring propagation delays only from the nearest points of regeneration.

In order to give maximum flexibility and minimum inter-node dependence, each node in the spread will generate timestamps using its RTC. Frames containing timestamps will also include values indicating the number of hops from, and the stratum value (e.g. clock quality) of, the spread synchronization master. These additional values will be used to auto configure a master—slave hierarchy with respect to clock adjustments, assuring that all RTCs in the spread converge towards that of the spread sync master. Each node in the spread—except the spread sync master—slaves itself to the neighbour providing the best acceptable timing information. Until timing information of an acceptable stratum becomes available, nodes remain unsynchronised.

**FIG. 5B** illustrates the flow of timing information in a fragment 550 of a spread having two backbones 552, 554 connected to the same synchronization master 556. The synchronization master 556 may be, for instance, a data collection system with access to a GPS receiver to provide a clock in the manner of the data collection system 506 and GPS receiver 502 in the embodiment of **FIG. 5A**. Returning to **FIG. 5B**, note that each of the synchronization master 556, and slaves 558, 560, 562, 564, 566 each have a RTC 568. Note that each of the slaves 562, 564, 566 are slaved to the RTC 568 of their neighbour, *i.e.*, the slaves 558, 562, and 564, respectively. The slaves 562, 564, 566 may be seismic data sources, data source nodes, routers, or data collection systems. The slaves 558, 560 are slaved to their neighbours, the slave 558 and the synchronization master 556, respectively. The slaves 558, 560, in the illustrated embodiment, are routers.

Each point of timestamp regeneration introduces a potential new source of clock drift and jitter. However, basic statistical principles dictate that in the absence of systematic errors the expected accumulated clock error grows only as the square root of the number regeneration points traversed, *i.e.*,  $\sqrt{n_{\text{hops}}}$ . Note that this is the same as for the embodiment of **FIG. 5A**. In the illustrated embodiment, there are no hops to the synchronization master 556, there is one hop to the slaves 558, 566, and there are two hops to the slaves 552, 562, and 564.

This "domino synchronization" scheme illustrated in **FIG. 5B** only measures propagation delay between immediate neighbours, as the timestamps used by a node to adjust its RTC will be generated by one of its neighbours. Because nodes synchronize themselves using only information from their immediate neighbours, the spread topology can change without seriously disrupting spread synchronization. The basic elements of the scheme are thus:

- auto configuration of the (nearest neighbour) master - slave hierarchy;
- regular propagation delay measurements between immediate neighbours; and
- RTC adjustments.

Note that this scheme provides fail over as for data traffic. More particularly, if the link between a node and the neighbour acting as its synchronization master fails, the node can switch to any other neighbour providing acceptable timing information. Note further that data collection systems connected to the spread network can be configured to be

synchronization clients, *e.g.* they can be accurately synchronized with the line nodes, and with other data collection systems without having their own time reference systems.

Turning now to the location mapping service, the order and orientations (*e.g.*, 180° rotations) of data source nodes N are determined to perform "peg mapping." That is, this information is determined to generate a mapping between seismic survey topology (*e.g.*, lines and receiver points) and network topology. The peg mapping is performed because the absence of true geographical positioning information for data source nodes N and their seismic data sources S. Peg mapping is not typically a part of open networking standards, although it is performed in conventional, proprietary protocols. Therefore an additional protocol—mapping node order, node orientation, and defining topology events—is used in conjunction with the open protocol. Topology events include: link up, link down (or node failure) plus node address change. Local location information is collected by the routers R and made available, as a service, to interested applications. Peg mapping techniques used on conventional proprietary networks may be employed for this purpose.

Finally, auto configuration of the network infrastructure simplifies flexible deployment and helps automate reconfiguration, *e.g.*, for spread roll and line fault recovery. The core of the auto configuration scheme employed in this particular embodiment is hierarchical addressing coupled with a hierarchy of configurable configuration servers that use contention to resolve conflicts. Note, however, that alternative addressing and contention approaches may be used in alternative embodiments.

Network addresses in the illustrated embodiment consist of a network number part and a node part in accordance with the open protocol applied as discussed above. Network numbers at a particular level in the hierarchy are generated by combining network and nodes numbers from the next higher level using what is basically a left shift (or promotion) of the node part. This addressing may be performed in conventional fashion.

The illustrated embodiment couples this hierarchical addressing with a hierarchy of configurable "configuration servers." The configuration servers also operate in a hierarchical fashion. Three levels of configuration servers are defined in the illustrated embodiment:



- a unique root server (with zero or more backup servers for redundancy), which allocates backbone numbers;
- backbone servers, one per backbone, which allocate backbone addresses having a network part based on backbone number; and
- line network servers, one per line network, which allocate line network addresses having a network part based on router backbone-port addresses.

Note that, in alternative embodiments, different levels may be employed in addition to, or in lieu of, those listed above.

For instance, referring now to FIG. 4, assume the data collection unit DC<sub>1</sub> has been designated as the unique root server. The data collection unit DC<sub>1</sub> configures itself and passes configuration information to the backbone servers. In the illustrated embodiment, the backbone servers would be the routers R<sub>0</sub>, R<sub>1</sub>, and R<sub>2</sub>. The backbone routers configure themselves and then pass configuration information on to the line network servers. For example, the routers R<sub>1</sub>, R<sub>2</sub>, R<sub>4</sub>, R<sub>5</sub>, R<sub>7</sub>, R<sub>8</sub>, R<sub>10</sub>, and R<sub>11</sub> may be line network servers. The line network servers then configure themselves. Note that the redundancy of the configuration in FIG. 4 provides an alternative configuration, as well. For instance, the data collection unit DC<sub>2</sub> may be the unique root server, the routers R<sub>2</sub>, R<sub>5</sub>, R<sub>8</sub>, and R<sub>11</sub> may be the backbone servers, and the routers R<sub>0</sub>, R<sub>1</sub>, R<sub>3</sub>, R<sub>4</sub>, R<sub>6</sub>, R<sub>7</sub>, R<sub>9</sub>, and R<sub>10</sub> may be the line network servers.

Conflicts between two peer-level configuration servers (*i.e.*, root *vs.* root, backbone *vs.* backbone, or line network *vs.* line network) are resolved through contention. In the illustrated embodiment, the greater of two unique numerical box identifiers wins. Consider, for instance, a scenario in which both the data collection unit DC<sub>1</sub> and the data collection unit DC<sub>2</sub> have both inadvertently been designated as the root server. This would be undesirable because they might assign the same addresses to different backbone routers or different addresses to the same backbone router. Once the data collection units DC<sub>1</sub>, DC<sub>2</sub> become aware of the conflict, they resolve the contention by comparing the unique identifiers. The data collection unit 140 having the lowest unique identifier backs off, and the other proceeds with the auto-configuration.

The unique identifiers can either be box serial numbers or some other unique identifier having the same format but which has been set by software. The source of the unique identifier is not material to the practice of the invention so long as each potential server's identifier is unique relative to the others. Note that the network addresses do not necessarily have anything to do with the unique identifiers used for resolving contention. The ability to set an arbitrary value by software can be used by a data collection system wishing to prevent complete reconfiguration of the spread as new nodes are added.

A configuration server keeps track of its immediate children. When, and if, a configuration server loses contention, it notifies its immediate children that they must restart before it terminates its services. The restarted children thus obtain new configuration information from the winning server. When a child server is asked to restart, it sends further notification to its children before doing so. In order to facilitate node tracking when contention results in reconfiguration, the location services will be notified, so that address updates can be published to interested applications.

Thus, in operation, and as shown in FIG. 6, a respective network address is assigned (at 605) to each one of the seismic data sources, data sources data source nodes, routers, and data collection systems. Typically, this is performed by the line or backbone server 135 ( $R_0$ ,  $R_1$ , or  $R_{20}$ ), although this is not necessary to the practice of the invention. Should two different pieces of equipment attempt to assign addresses, the conflict is, in the illustrated embodiment, resolved through contention as described above. The addresses are assigned (at 605) each time the network infrastructure is configured. Thus, the addresses may be assigned (at 605) either upon power-up as the recording array is deployed, or upon reset, *i.e.*, when the network infrastructure is automatically reconfigured for, *e.g.*, a link going down or coming up.

Once the network infrastructure is up and running, with addresses assigned (at 605), data generated by the data sources is routed (at 610) through the data source nodes and the routers to a data collection system. The manner in which the data is packaged by the seismic data sources and routed will be implementation specific, depending on the particular open protocol in use. Again, the illustrated embodiment employs the IP protocol as its open protocol, but others may be used in alternative embodiments. Operation of the network

infrastructure is synchronized as was described above using, in the illustrated embodiment, the NTP protocol.

The collected data is then processed. The processing involves first correlating the network addresses of the seismic data sources to the logical location of the respective seismic data sources (at 615). This involves first peg mapping the network addresses of the seismic data sources to their logical location in the recording array, as was discussed above. Next, the logical locations of the respective seismic data sources to the data generated by the respective seismic data sources is correlated (at 620). Ordinarily, the data is transmitted from the seismic data sources to the data collection system in packets. Each packet typically includes not only data, but a header that includes information such as the source and destination network addresses of the packet. Thus, the source network address can be extracted from the header of the packet and, having already been correlated to the logical location (at 615), the logical location can then readily be correlated to the data (at 620).

**FIG. 7A** and **FIG. 7B** illustrate the use of the present invention in a land-based seismic survey. **FIG. 7A** shows the seismic recording array 110, first shown in **FIG. 1**, connected to the recording truck 105. The seismic source 115 is also shown. The data collection system 140 is shown centrally located on the recording truck 105. However, as will be appreciated by those skilled in the art, various portions of the data collection system 140 may be distributed, *e.g.*, across the recording array 110, in alternative embodiments.

Once the recording array 110 is assembled and deployed, a network address is assigned (at 710, **FIG. 7B**) in accordance with an open network protocol to each one of a plurality of seismic data sources 120, data source nodes 130, and routers 135 (all shown in **FIG. 1**). The seismic source 115 generates a plurality of seismic survey signals 715 (at 718, in **FIG. 7B**) in accordance with conventional practice. The seismic survey signals 715 propagate and are reflected by the subterranean geological formation 725. The seismic data sources 120 receive (at 730, **FIG. 7B**) the reflected signals 735 of the generated signals 715. Note that, although not shown, some of the seismic data sources 120 are also receiving positioning signals, *e.g.*, GPS signals, in accordance with conventional practice.

The seismic data sources 120 then generate (at 738, in FIG. 7B) data representative of the reflections 735. In the illustrated embodiment, the seismic data sources 120 receiving positioning signals also generate data representative of the received positioning signals. The generated data is then routed (at 740, in FIG. 7B) from the seismic data sources 120 through the data source nodes 130 and the routers 135 to the data collection system 140 in accordance with the open network protocol. The data collection system 140 collects the data for processing. The data collection system 140 may process the data itself, store the data for processing at a later time, or transmit the data to a remote location for processing.

In the illustrated embodiment, the data collection system 140 processes the data itself. The data collection system 140 correlates the network addresses (at 745, in FIG. 7B) of the seismic data sources 120 to the physical location of the respective seismic data sources 120. This involves first determining the logical location of the network address in the recording array 110 using the peg mapping service as was described above. The actual position of the logical location is then determined. The determination of the actual position may be performed using any technique known to the art suitable to the seismic data sources being implemented and the data they generate. The physical locations of the respective seismic data sources 120 are then correlated (at 750, in FIG. 7B) to the data generated by the respective seismic data sources 120. The data is then used to develop (at 755, in FIG. 7B) a representation of the subterranean formation 725 from the data.

Some portions of the detailed descriptions herein are presented in terms of a software implemented process involving symbolic representations of operations on data bits within a memory in a computing system or a computing device. These descriptions and representations are the means used by those in the art to most effectively convey the substance of their work to others skilled in the art. The process and operation require physical manipulations of physical quantities. Usually, though not necessarily, these quantities take the form of electrical, magnetic, or optical signals capable of being stored, transferred, combined, compared, and otherwise manipulated. It has proven convenient at times, principally for reasons of common usage, to refer to these signals as bits, values, elements, symbols, characters, terms, numbers, or the like.

It should be borne in mind, however, that all of these and similar terms are to be associated with the appropriate physical quantities and are merely convenient labels applied to these quantities. Unless specifically stated or otherwise as may be apparent, throughout the present disclosure, these descriptions refer to the action and processes of an electronic device, that manipulates and transforms data represented as physical (electronic, magnetic, or optical) quantities within some electronic device's storage into other data similarly represented as physical quantities within the storage, or in transmission or display devices. Exemplary of the terms denoting such a description are, without limitation, the terms "processing," "computing," "calculating," "determining," "displaying," and the like.

Note also that the software implemented aspects of the invention are typically encoded on some form of program storage medium or implemented over some type of transmission medium. The program storage medium may be magnetic (e.g., a floppy disk or a hard drive) or optical (e.g., a compact disk read only memory, or "CD ROM"), and may be read only or random access. Similarly, the transmission medium may be twisted wire pairs, coaxial cable, optical fibre, or some other suitable transmission medium known to the art. The invention is not limited by these aspects of any given implementation.

This concludes the detailed description. The particular embodiments disclosed above are illustrative only, as the invention may be modified and practiced in different but equivalent manners apparent to those skilled in the art having the benefit of the teachings herein. Furthermore, no limitations are intended to the details of construction or design herein shown, other than as described in the claims below. For instance, although the illustrated embodiment employs the invention in the context of a land-based survey, alternative embodiments may implement the invention seabed acquisition. In this alternative embodiment, the seismic data sources might include seismic sources such as a vibrator or an explosive charge, seismic receivers such as geophones, and positioning instruments such as GPS receivers. It is therefore evident that the particular embodiments disclosed above may be altered or modified and all such variations are considered within the scope and spirit of the invention. Accordingly, the protection sought herein is as set forth in the claims below.

**CLAIMS:**

1. A seismic acquisition system, comprising:  
a plurality of seismic data sources capable of generating data;  
at least one data collection system utilizing an open network protocol; and  
at least one line network connecting the data sources to the data collection system and  
utilizing an open network protocol, the line network including:  
a plurality of data source nodes at which a portion of the plurality of seismic  
data sources are respectively attached to the line network; and  
a router for routing data generated by the seismic data sources to the data  
collection system through the data source nodes in accordance with the  
open network protocol.
2. The seismic acquisition system of claim 1, wherein the router routes data to  
the seismic data sources.
3. The seismic acquisition system of claim 1, wherein each of the data source  
nodes is assigned at least two respective network addresses under the open network protocol.
4. The seismic acquisition system of claim 1, further comprising at least one  
additional router for routing data generated by the seismic data sources to the data collection  
system through the data source nodes in accordance with the open network protocol.
5. The seismic acquisition system of claim 1, wherein the data collection system  
is assigned at least two respective network addresses under the open network protocol.
6. The seismic acquisition system of claim 1, wherein the seismic cable  
comprises a land-based seismic cable or an ocean bottom cable.
7. The seismic acquisition system of claim 1, wherein the seismic data sources  
include at least one of seismic sources, seismic receivers, and positioning instruments.
8. The seismic acquisition system of claim 7, where in the seismic sources  
include at least one of an air gun, a vibrator, and an explosive charge.
9. The seismic acquisition system of claim 7, wherein the seismic receivers  
include at least one of a hydrophone and a geophone.

10. The seismic acquisition system of claim 1, wherein the open network protocol includes the Internet Protocol.

11. The seismic acquisition system of claim 10, further comprising a synchronization service.

12. The seismic acquisition system of claim 11, wherein the synchronization service comprises the Network Time Protocol.

13. The seismic acquisition system of claim 1, wherein the at least one data collection system further administers at least one of:

a synchronization service synchronizing a plurality of clocks for the data collection system, the router, the data source nodes, and the seismic data sources;

a location mapping service for mapping between network addresses and logical locations of the data collection system, the router, the data source nodes, and the seismic data sources; and

an auto-configuration capability for automatically reconfiguring the network upon removal of any one of the router, the data source nodes, or the seismic data sources, or upon the addition of an additional piece of seismic equipment.

14. The seismic acquisition system of claim 13, wherein the synchronization service comprises the Network Time Protocol.

15. The seismic acquisition network of claim 13, wherein the synchronization service tolerates changes in topology.

16. The seismic acquisition system of claim 13, wherein the synchronization service synchronizes the clocks hierarchically.

17. The seismic acquisition network of claim 13, wherein the synchronization service tolerates breaks in the attachment between at least one seismic data source and the line network.

18. The seismic acquisition system of claim 13, wherein the location mapping service maps:

an order for the data collection system, the router, the data source nodes, and the seismic data sources;

an orientation for each of the data collection system, the router, the data source nodes, and the seismic data sources; and

a plurality of topology events.

19. The seismic acquisition system of claim 18, wherein the topology events include at least one of a link going up, a link going down, and a node address change.

20. The seismic acquisition system of claim 13, wherein the at least one data collection system comprises a plurality of data collection systems and the synchronization service, the location mapping service, and the auto-configuration capability are administered by more than one of the plurality of data collection systems.

21. A method for use in a seismic survey, the method comprising:  
assigning at least two respective network addresses to each one of a plurality of seismic data sources, a plurality of data source nodes, a plurality of routers, and a data collection system;  
routing data generated by the data sources through the data source nodes and the routers to the data collection system;  
correlating the network addresses of the seismic data sources to the physical location of the respective seismic data sources; and  
correlating the physical locations of the respective seismic data sources to the data generated by the respective seismic data sources.

22. The method of claim 21, wherein assigning the at least two respective network addresses to each one of a plurality of seismic data sources includes assigning at least two respective network addresses to each one of a plurality of seismic data sources including at least one of a seismic source, a seismic receiver, and a positioning instrument.

23. The method of claim 21, further comprising at least one of:  
synchronizing a plurality of clocks for the data collection system, the router, the data source nodes, and the seismic data sources;  
mapping between network addresses and logical locations of the data collection system, the router, the data source nodes, and the seismic data sources; and



automatically reconfiguring the network upon removal of any one of the router, the data source nodes, or the seismic data sources, or upon the addition of an additional piece of seismic equipment.

24. The method of claim 23, wherein synchronizing the plurality of clocks includes synchronizing the clocks hierarchically.

25. The method of claim 23, wherein mapping between network addresses and logical locations of the data collection system includes:

mapping an order for the data collection system, the router, the data source nodes, and the seismic data sources;

mapping an orientation for each of the data collection system, the router, the data source nodes, and the seismic data sources; and

mapping a plurality of topology events.

## IMPLEMENTING A NETWORK INFRASTRUCTURE IN A SEISMIC ACQUISITION SYSTEM

### ABSTRACT

A method and apparatus implementing a network infrastructure in a seismic acquisition system are disclosed. The apparatus is a seismic acquisition system, comprising a plurality of seismic data sources (120) capable of generating data; at least one data collection system (140) utilizing an open network protocol; and at least one line network (300) connecting the data sources to the data collection system and utilizing an open network protocol. The line network(300) includes a plurality of data source nodes (130) at which a portion of the plurality of seismic data sources are respectively attached to the line network; and a router (135) for routing data generated by the seismic data sources (120) to the data collection system (140) through the data source nodes (130) in accordance with the open network protocol. The method comprises assigning at least two respective network addresses to each one of a plurality of seismic data sources, a plurality of data source nodes, a plurality of routers, and a data collection system; routing data generated by the data sources through the data source nodes and the routers to the data collection system; correlating the network addresses of the seismic data sources to the physical location of the respective seismic data sources; and correlating the physical locations of the respective seismic data sources to the data generated by the respective seismic data sources.

[Figure 3]

1 / 8




FIG. 1

218




FIG. 2A




FIG. 2B

3 / 8




FIG. 3




FIG. 6





FIG. 4



500 →

FIG. 5A





FIG. 5B



718

**FIG. 7A**




FIG. 7B